BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED

SECTION- IX

VOLUME-II

Bill of Quantities (BOQ)

PART-I SUPPLY PORTION				
SL No	**Particulars**	**Unit**	**Total Qty**	**Material Code**
1	Supply & Erection of PSCC pole 9 mtr long 300 kg W/L (for dead end and anchor points only)	No	**4**	200005
2	Supply & Erection of PSCC pole 9 mtr long 200kg W/L (for intermediate only)	No	**54**	200006
3	Supply & Erection of 11 kV, Horizontal Cross Arm with clamps, HTST supports, bolts, nuts and washers for PSCC Pole - 9 Mtr Long, 200 Kg WL-GI	set	**74**	CDS materials for General works
4	Supply & Providing of 45KN Composite polymer insulators.	No	**69**	283320
5	Supply & Providing of 11kV Composite Polymer pins insulators.(24mm dia FRP rod)	No	**174**	283008
6	Supply & Providing of Guy Set Complete with No. 15 Strain Insulator & Concreting materials-GI	set	**39**	CDS materials for General works
7	Supply & stringing of ACSR Rabbit conductor with 1.5% sag as per BESCOM Specification	Km	**10.521**	284108
8	Supply & Providing of Spiral Earth Electrode	No	**64**	281683
9	Supply & erection of DP set (2 pole structure kit-GI) with 9 mtr PSCC, 300 KG W/L including 5Kg , 8SWG GI wire for structure grounding.	set	**1**	CDS 46
10	Supply & providing of 11kV class 200 AMPS Single Break GOS	Set	**4**	304212
11	Supply & providing of H - Frame Set for 11kV, 200Amps Single Break GOS Mounting - GI	Set	**1**	280149
12	Supply & providing of 11kV Class DOLO Cutouts	Set (3 Nos)	**4**	302011
13	Supply & providing of caution/Danger board as per drawing no.BESCOM/GM/CP/40/24.10.17	No	**7**	613050
14	Supply & Fixing of Anticlimbing Device GI Barbed Wire (12 mtrs/1kg)Lumpsum	Kg	**12**	278911
15	Supply & Erection of Double Pole Mounted Transformer kit for 63 kVA with 2 Nos of 9 mtr long PSCC Pole, 300KG W/L- GI	Set	**1**	CDS materials for General works
16	Supply & Erection of 11kV/433V, 63 kVA,3phase 50cys Distribution Transformer BEE-4star rated	No	**1**	321438
17	Supply & providing of Earthing materials pipe type for grounding as per Drawing No BESCOM/GM/CP/15&34 dt:24.10.17(Single	No	**17**	281674+600095+607054, CDS

	Electrode with accessories)			60
18	Supply & providing of GI wire 8SWG	kg	**40**	281008
19	Supply & providing of Guy wire 7/10SWG	kg	**80**	281110
20	Supply & providing of 11kV lightning arrestors, poliymer Type,9kV 5 kA (Set=3No)	Set	**7**	303202, CDS 60
21	Supply & providing of LT Protection kit	No	**8**	301107
22	Supply & providing of LT wiring (from 63 KVA DTC to LT line)		**1**	
	i) Al Lead Wire - 95 Sqmm	Mtr	**30**	289031
	ii) Heavy Duty Long Barrel Copper Lug - 95 Sqmm	No	**12**	288531
	iii) PG Clamp - Rabbit to 95 Sqmm	No	**10**	285508, CDS 60
	iv) Spacer for DTC Wiring	No	**3**	284503
	v) Fish Plate with necessary Clamps, bolts & nuts etc complete (Galvanised)	No	**2**	280800+280511, CDS 60
	vi) LT Metering box with CTs and necessary wiring for housing ETV Meter (Please see CDS - 39)	No	**0**	CDS 39
23	Supply & providing of H.G.Fuse unit,11kV solid core Type(Set=3no)	Set	**3**	302122
24	supply & providing Transparent Alkathine tube 19mm dia, 2mm thick in coils of 30 mtrs	Coil	**7**	821900
25	Supply & Erection of 9M PSCC pole WL 300Kg	No	**10**	200005
26	Supply & Erection of Single Pole Mounted Transformer kit for 25 kVA on 9 mtr PSCC Poles of 300kG WL --GI with H-frame	Set	**2**	280119, CDS materials for General works
27	Supply & Erection of 11kV/433V, 25 kVA,3phase 50cys Distribution Transformer BEE-4star rated	No	**6**	321437
28	Supply & providing of LT wiring (from 25 KVA DTC to LT line)		**2**	
a	Aluminium lead wire 50 sqmm	Mtr	**140**	289031
b	Heavy duty long barrel copper lugs- 50 sqmm	No	**36**	288531
c	P.G Clamps - Rabbit to 50 sq.mm	No	**16**	285508, CDS 63
d	Fish Plate with necessary Clamps, bolts & nuts etc complete (Galvanised)	No	**10**	280800+280511, CDS 63
e	Spacers for DTC wiring	No	**18**	284503
f	LT Metering box with CTs and necessary wiring for housing ETV Meter (Please see CDS - 39)	No	**0**	CDS 39
29	PSCC Pole - 8 Mtr Long, 200 Kg WL (for Intermediate Pole)	No	**8**	200004
30	LT 4 Pin Cross Arm with clamps, bolts, nuts and washers for PSCC Pole - 8 Mtr Long, 200 Kg WL-GI	Set	**11**	280014, CDS materials for General

				works
31	LT 2 Pin Cross Arm with clamps, bolts, nuts for PSCC Pole - 8 Mtr Long, 200 Kg WL- GI	Set	**5**	280012, CDS materials for General works
32	1.1 kV Pin Insulator with GI Pin	No	**20**	283053, CDS 5
33	No. 8 Strain Insulator	No	**40**	283158
34	Supply & Providing of Guy Set Complete with No 8. Strain Insulator & Concreting materials-GI	Set	**10**	CDS materials for General works
35	Sheet Metal/Deep Drawn Street Lighting Metering Box with Automatic Control Swith, Contactors with Single Phase 5-30 Amps Meter & 50/5A CT including wiring	No	**2**	CDS 69
36	PVC Pipe 40 mm Dia	Mtr	**20**	CDS 69
37	PVC Insulated wire 25 Sqmm Single Core Multi Stranded	Mtr	**20**	CDS 69
38	1.1kV Class 3 Phase Aerial Bunched Cable of size 3x95+1x16+1x70 Sq. mm	**KMs**	**1**	CDS 37
39	PSCC Pole - 8 Mtr Long, 200 Kg WL (for Intermediate Pole)	No's	**3**	200004
40	Three Phase Distribution box for 6 Connections	No's	**3**	CDS 37
41	Piercing connector suitable for 16 Sq. mm - 95 Sq. mm AB Cable - Service Connections	No's	**10**	CDS 37
42	Piercing connector suitable for 16 Sq. mm - 95 Sq. mm AB Cable - Street Light Connections	No's	**10**	CDS 37
43	Suspension Clamp Assembly 16 to 70 mm (Excluding pole clamp & Eye Hook)	Sets	**5**	CDS 37
44	Pole clamp for HT/LT AB cable	Sets	**5**	CDS 37
45	Eye Hook (Flat type) for fixing Clamps	Sets	**4**	CDS 37
46	Dead End Clamp/Anchor Clamp Assembly 25 to 95 Sq mm (excluding pole clamps and Eye hook)	Sets	**2**	CDS 37
47	Universal Hook, Bolts & nuts	No's	**4**	CDS 37
48	T-connector KZ3 95	No's	**4**	CDS 37
49	Cable Straight thru' joint kits suitable for 95 Sqmm	Sets	**1**	CDS 37
50	Pre-Insulated lugs-CPTAU for 95 Sqmm	No's	**3**	CDS 37
51	End cap for 50/70 Sqmm	No's	**3**	CDS 37
52	Supply & Providing of Guy Set Complete with No 8. Strain Insulator & Concreting materials-GI	Sets	**3**	CDS 37
53	PVC Insulated wire 16/25 Sqmm	Mtrs	**10**	CDS 37

PART-II ERECTION PORTION

SL No	Particulars	Unit	Total Qty
1	Supply & Erection of PSCC pole 9 mtr long 300 kg W/L (for dead end and anchor points only)	No	**4**
2	Supply & Erection of PSCC pole 9 mtr long 200kg W/L (for intermediate only)	No	**54**
3	Supply & Erection of 11 kV, Horizontal Cross Arm with clamps, HTST supports, bolts, nuts and washers for PSCC Pole - 9 Mtr Long, 200 Kg WL-GI	set	**74**
4	Supply & Providing of Guy Set Complete with No. 15 Strain Insulator & Concreting materials-GI	set	**39**
5	Supply & stringing of ACSR Rabbit conductor with 1.5% sag as per BESCOM Specification	Km	**10.521**
6	Supply & Providing of Spiral Earth Electrode	No	**64**
7	Supply & erection of DP set (2 pole structure kit-GI) with 9 mtr PSCC, 300 KG W/L including 5Kg , 8SWG GI wire for structure grounding.	set	**1**
8	Supply & providing of 11kV class 200 AMPS Single Break GOS	Set	**4**
9	Supply & providing of H - Frame Set for 11kV, 200Amps Single Break GOS Mounting - GI	Set	**1**
10	Supply & providing of 11kV Class DOLO Cutouts	Set (3 Nos)	**4**
11	Supply & providing of caution/Danger board as per drawing no.BESCOM/GM/CP/40/24.10.17	No	**7**
12	Supply & Fixing of Anticlimbing Device GI Barbed Wire (12 mtrs/1kg)Lumpsum	Kg	**12**
13	Supply & Erection of Double Pole Mounted Transformer kit for 63 kVA with 2 Nos of 9 mtr long PSCC Pole, 300KG W/L- GI	Set	**1**
14	Supply & Erection of 11kV/433V, 63 kVA,3phase 50cys Distribution Transformer BEE-4star rated	No	**1**
15	Supply & providing of Earthing materials pipe type for grounding as per Drawing No BESCOM/GM/CP/15&34 dt:24.10.17(Single Electrode with accessories)	No	**17**
16	Supply & providing of 11kV lightning arrestors, poliymer Type,9kV 5 kA (Set=3No)	Set	**7**
17	Supply & providing of LT Protection kit	No	**8**
18	Supply & providing of LT wiring (from 63 KVA DTC to LT line)		**1**

	i) Al Lead Wire - 95 Sqmm	Mtr	**30**
	ii) Heavy Duty Long Barrel Copper Lug - 95 Sqmm	No	**12**
	iii) PG Clamp - Rabbit to 95 Sqmm	No	**10**
	iv) Spacer for DTC Wiring	No	**3**
	v) Fish Plate with necessary Clamps, bolts & nuts etc complete (Galvanised)	No	**2**
	vi) LT Metering box with CTs and necessary wiring for housing ETV Meter (Please see CDS - 39)	No	**0**
19	Supply & providing of H.G.Fuse unit,11kV solid core Type(Set=3no)	Set	**3**
20	Supply & Erection of 9M PSCC pole WL 300Kg	No	**10**
21	Supply & Erection of Single Pole Mounted Transformer kit for 25 kVA on 9 mtr PSCC Poles of 300kG WL --GI with H-frame	Set	**2**
22	Supply & Erection of 11kV/433V, 25 kVA,3phase 50cys Distribution Transformer BEE-4star rated	No	**6**
23	Supply & providing of LT wiring (from 25 KVA DTC to LT line)		**2**
a	Aluminium lead wire 50 sqmm	Mtr	**140**
b	Heavy duty long barrel copper lugs- 50 sqmm	No	**36**
c	P.G Clamps - Rabbit to 50 sq.mm	No	**16**
d	Fish Plate with necessary Clamps, bolts & nuts etc complete (Galvanised)	No	**10**
e	Spacers for DTC wiring	No	**18**
f	LT Metering box with CTs and necessary wiring for housing ETV Meter (Please see CDS - 39)	No	**0**
24	PSCC Pole - 8 Mtr Long, 200 Kg WL (for Intermediate Pole)	No	**8**
25	LT 4 Pin Cross Arm with clamps, bolts, nuts and washers for PSCC Pole - 8 Mtr Long, 200 Kg WL-GI	Set	**11**
26	LT 2 Pin Cross Arm with clamps, bolts, nuts for PSCC Pole - 8 Mtr Long, 200 Kg WL- GI	Set	**5**
27	Supply & Providing of Guy Set Complete with No 8. Strain Insulator & Concreting materials-GI	Set	**10**
28	Guy concreting with Boulders, Mud and Sand	No	**4**
29	Sheet Metal/Deep Drawn Street Lighting Metering Box with Automatic Control Swith, Contactors with Single Phase 5-30 Amps Meter & 50/5A CT including wiring	No	**2**

30	1.1kV Class 3 Phase Aerial Bunched Cable of size 3x95+1x16+1x70 Sq. mm	**KMs**	**1**
31	PSCC Pole - 8 Mtr Long, 200 Kg WL (for Intermediate Pole)	No's	**3**
32	Three Phase Distribution box for 6 Connections	No's	**3**
33	Piercing connector suitable for 16 Sq. mm - 95 Sq. mm AB Cable - Service Connections	No's	**10**
34	Piercing connector suitable for 16 Sq. mm - 95 Sq. mm AB Cable - Street Light Connections	No's	**10**
35	Suspension Clamp Assembly 16 to 70 mm (Excluding pole clamp & Eye Hook)	Sets	**5**
36	Pole clamp for HT/LT AB cable	Sets	**5**
37	Dead End Clamp/Anchor Clamp Assembly 25 to 95 Sq mm (excluding pole clamps and Eye hook)	Sets	**2**
38	Universal Hook, Bolts & nuts	No's	**4**
39	T-connector KZ3 95	No's	**4**
40	Cable Straight thru' joint kits suitable for 95 Sqmm	Sets	**1**
41	Pre-Insulated lugs-CPTAU for 95 Sqmm	No's	**3**
42	End cap for 50/70 Sqmm	No's	**3**
43	Supply & Providing of Guy Set Complete with No 8. Strain Insulator & Concreting materials-GI	Sets	**3**
44	Guy Concreting with Mud, Boulders & Sand	Sets	**3**